BRUHATH BANGALORE MAHANAGARA PALIKE.

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/OW/WORK_INDENT50539

Name of Work: De-silting and Re-setting of drain and Re asphalting toSiddeshwara layout in Bagalagunte ward no 14.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri GOVINDARAJU CHIKKAVENKATAPPA (DHRUVIT CONSTRUCTIONS)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	525.84	180.46	Rupees One Hundred Eighty and Forty Six Paise Only
2	Providing and laying in position plain cement concrete of mix1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	87.64	5143.66	Rupees Five Thousand One Hundred Forty Three and Sixty Six Paise Only
3	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications.	Sqm	1003.77	360.92	Rupees Three Hundred Sixty and Ninety Two Paise Only

Signature of the Contractor,

Executive Engineer
Dasarahalli Division

4	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6	Cum	189.89	5705.21	Rupees Five Thousand Seven Hundred Five and Twenty One Paise Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Tonne	11.39	88130.85	Rupees Eighty Eight Thousand One Hundred Thirty and Eighty Five Paise Only
6	Providing and and fixing Precast Concrete slab 10 CM thick witth all lead and lift as per specification	Sqm	486.89	2222.72	Rupees Two Thousand Two Hundred Twenty Two and Seventy Two Paise Only
7	Transportation &disposing of the excavated earth obtained from side drains and high burms on either side of the road	Sqm	525.84	81.46	Rupees Eighty One and Forty Six Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,